



**NOTES:**

1. A RECTANGULAR VAULT IS REQD WHERE TELEMETRY OR ELECTRICAL EQUIPMENT IS ANTICIPATED INSIDE THE VAULT.
2. ACCESS STAIRS WITH DOOR OUTSIDE OF PAVEMENT MAY BE REQD ON STREETS WITH HEAVY TRAFFIC.
3. FOR CROSS SECTION VIEW, SEE CROSS SECTION SHEET 44.
4. DO NOT PLACE SUMP DIRECTLY UNDER MH.
5. THIS MH IS SUITABLE FOR CHECK VALVE INSTALLATIONS.
6. PIPING FOR PRV AND CHECK VALVE INSTALLATIONS SHALL BE DI.
7. LADDER RUNGS ARE REQD IN PRE-CAST MH. THE DISTANCE BETWEEN RUNGS, CLEATS, AND STEPS SHALL NOT EXCEED 12" AND SHALL BE UNIFORM THROUGHOUT THE LENGTH OF THE LADDER.

**ARAPAHOE COUNTY**  
 Water and Wastewater Authority  
 13031 E Caley Ave, Centennial, Colorado 80111  
 Ph: (303) 790-4830 Fax: (303) 790-1718  
 © Copyright 2007 All Rights Reserved

**PRESSURE REGULATING VALVE  
 MANHOLE INSTALLATION TYPICAL  
 PLAN**

REVISION DATE: 9/7/2005
FIGURE NO. <b>W-19</b>
SHEET NO. 1 of 1